

## KADUR DIVISION.

## ADVERTISEMENT.

*The 17th May 1892.*

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 5th June 1892, for restoring the Devanur Tank, Registered No. 209, Kadur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1893.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring the Devanur Tank, Kadur Taluk"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of Work.			Per.	Quantity.	Rate.
<i>Bund—</i>					
Earthwork, watering and tamping ..	..	..	C. Yd.	25,000	
Old stone work, dry, dismantling and building..	..	..	Do	2,652	
New stone work, dry ..	..	..	Do	2,500	
Do do ..	..	..	Do	3,308	
Grade stones as per standard design ..	..	..	Each.	61	
Bench Mark stones ..	..	..	Do	2	
Turfing front slope ..	..	..	Sq. Yd.	3,150	
<i>Waste Weir, No. I, 30 ft. long—</i>					
New stone work, dry..	..	..	C. Yd.	57	
Brick in surki mortar ..	..	..	C. Ft.	900	
Excavating foundation ..	..	..	Lump Sum.		
Plastering with chunam ..	..	..	Sqr.	300	
Burnt stone slabs set in mortar ..	..	..	S. Ft.	92	
<i>Waste Weir, No. II, 270 ft. long—</i>					
New stone work ..	..	..	C. Yd.	263	
Old stone work, dry, dismantling and rebuilding ..	..	..	Do	495	
Brick in surki mortar ..	..	..	C. Ft.	4,022	
Plastering with chunam ..	..	..	Sqr.	2900	
Burnt stone slabs set in mortar ..	..	..	Sq. Ft.	536	
Excavating foundation, &c. ..	..	..	C. Yd.	802	
<i>Sluices—</i>					
Repairing the Sluices Nos. 1, 2 and 3 ..	..	..	Lump Sum	Rs.	

A. GOVINDACHARLU,  
Executive Engineer.

*The 9th May 1892.*

## NOTICE.

Is hereby given that a sum of Rs. 58—2—2 is due to late Task Worker Lazarus of Shimoga for work executed by him on constructing Sandal-Koti at Sagar. The amount will be paid to such heir or heirs of the deceased as would produce a heirship certificate before the undersigned within 2 months from this date. If no claims be made within the prescribed period, the amount will be forfeited to Government

S. VENKATACHARIAR,  
Exe. Engr., Shimoga Division.